

SURVEY & REMONUMENTATION

JUN 29 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
2ND day of MARCH
 A. D. 1995 at 9:10 o'clock
A m., and recorded in
 Liber 5 of CORNERS
 on page 211.
Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in _____
Gogebic
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>46N</u> R <u>42W</u>	<u>B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____
 1/4 Corner 18 & 19; T.46N., R.42W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard L. Drahn, in a field survey on June 9, _____, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by A. Merryweather, U.S. Deputy Surveyor, on August 18, 1851. Original bearing trees:

Cedar	8"	S.40W.	25 links	(16.50 feet)
Cedar	6"	N.23E.	11 links	(7.26 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No G.L.O. evidence remains. Corner position re-established on line between and proportionate distance from the southeast and southwest section corners of Section 18; T.46N., R.42W.



PEER GROUP APPROVED
Richard L. Drahn 3/1/95
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" x 3 foot solid aluminum marsh rod with a 3 1/4" aluminum cap with magnet stamped to read: T.46N., R.42W.; 1/4; S-18, S-19; 1994; R.L.S. 21564 from which I established the following new blazed and scribed bearing trees and/or objects:

12"	Cedar	N.10E.	57.18 feet
8"	Red Maple	N.80E.	23.78 feet
10"	Yellow Birch	S.19W.	22.98 feet
6'	Steel Rail	N.20E.	2.08 feet

Signed by Richard L. Drahn
 21564

Date February 6, 1995

Surveyor's Michigan License No. _____

USFS #N-3