

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Gogebic

Located In:	Corner Code #
Section 7 46N 42W C-4	
1. Public Land Survey	T R
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

Register's Office }
Gogebic County } ss.

Received for record the
14TH day of MAY
A. D. 19 98 at 3:00 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 331
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 corner to sections 7 & 8, T46N, R42W

I, John R. Garske, in a field survey on February 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner set by Algermon Merriweather D.S. in 1851

Original BTS:

Balsam 8" S25°E 21 links

Birch 12" N70°W 30 links

Corner restored by Richard Drahn, RLS, Feb. 2, 1978 from the remains of the two original bearing trees. He established new BT's as noted below and set a 2" I.D. x 36" long concrete filled galv. pipe capped with a 3" brass tablet stamped to identify the corner. He recorded the corner in Liber 1, pg.359.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found Mr. Drahn's corner monument in good condition along with his bearing trees:

(4") 6" sugar N57°W 37.08 (37.0')

(5") 6" sugar N04°E 20.65 (20.6')

(5") 6" sugar S79°E 37.52 (37.5')

Steel sign rail N79°E 1.56 (1.6')

(Research on file)

() - Recorded Data

PEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY Barabeno

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 2" I D galv. pipe with 3" dia. brass cap stamped to identify the corner.

New accessories:

Power pole #793/49 S09°W 36.64 feet

M-64 South 83.50 feet



Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 5/12/98