

map  
COMP

# SURVEY & REMONUMENTATION

JUN 29 1995

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
2<sup>ND</sup> day of MARCH  
A. D. 1995 at 9:10 o'clock  
A m., and recorded in  
Liber 5 of CORNERS  
on page 215  
Bonana Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>42W</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 Section Corner 8,9,16 & 17; T.46N. R.42W.

I, Richard L. Drahn, in a field survey on July 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner established by A. Merryweather, U.S. Deputy Surveyor; on August 19, 1851. Original bearing trees:  
 Balsam 12" S.80E. 12 links (7.92 feet)  
 Elm 10" N.40W. 20 links (13.20 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Restored corner position from the stump remains of the original Elm bearing tree. Distance north and west to stream call checks. Distance south and west to recovered section corners is in accordance with the field notes of the original survey.

PEER GROUP APPROVED  
Richard L. Drahn 3/1/95  
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 At the corner position I set a 2 1/2" diameter by 30" long aluminum monument with a 3 1/4" aluminum cap with magnet stamped to read T.46N., R.42W.; S-8, S-9, S-16, S-17; 1994 R.L.S. 21564 from which I established the following new blazed and scribed bearing trees and/or objects:

7"	Sugar Maple	N.12W.	15.56 feet
8"	Sugar Maple	S.23E.	15.19 feet
7"	Sugar Maple	S.63W.	33.21 feet
6'	Steel Rail	S.05W.	2.40 feet



Signed by Richard L. Drahn Date February 6, 1995  
 Surveyor's Michigan License No. 21564