

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Gogebic County

| FOR CORNERS OF--:                          | LOCATED IN--:                    | CORNER CODE NUMBER |
|--|----------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. 46 N. 3/4, R. 42 W.           | G-1                |
| 2. PROPERTY CONTROLLING IN SECTION _____   | , T. _____ N. S., R. _____ E. W. | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ N. S., R. _____ E. W. | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____      |                                  |                    |
| 5. PRIVATE CLAIMS _____                    |                                  |                    |

Register's Office }  
Gogebic County } ss.

Received for record the  
4<sup>th</sup> day of January  
A. D. 1993 at 2:00 o'clock  
P m., and recorded in  
Liber 4 of Corners  
on page 118  
Richard J. Brouwer  
Register of Deeds

REGISTER OF DEEDS STAMP AND FILING NUMBER

**PEER GROUP**

Approved

Richard L. Drahn  
1/20/94

I, Richard L. Drahn do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 18 1992, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established by William Burt, U.S. Deputy Surveyor in 1847.

Original bearing trees:

|       |     |                      |          |              |
|-------|-----|----------------------|----------|--------------|
| Sugar | 24" | N.09 <sup>o</sup> E. | 31 links | (20.46 feet) |
| Sugar | 20" | N.63 <sup>o</sup> W. | 35 links | (23.10 feet) |
| Lynn  | 16" | S.55 <sup>o</sup> W. | 24 links | (15.84 feet) |
| Sugar | 10" | S.28 <sup>o</sup> E. | 27 links | (17.82 feet) |

Monument box established by M. Dot in M-64. Numerous lot and plat references to this corner position.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Bearing trees established by Jack Goss, R.L.S., in 1979:

|     |       |                      |            |   |
|-----|-------|----------------------|------------|---|
| 12" | Maple | N.67 <sup>o</sup> W. | 71.93 feet |   |
| 8"  | Elm   | S.71 <sup>o</sup> W. | 63.99 feet | (actually <del>an Elm</del> <b>A Ironwood</b> ) |
| 13" | Maple | S.48 <sup>o</sup> W. | 86.74 feet |   |

Original bearing trees destroyed by road construction. Recovered the States monumentation box and Jack Goss's bearing trees as recorded.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At a point on the section line 60.99 feet west of the section corner, I set an aluminum split base Witness Corner. From the monumentation box in M-64, I established the new blazed and scribed bearing trees:

|     |             |                      |            |  |
|-----|-------------|----------------------|------------|--|
| 12" | Sugar Maple | N.88 <sup>o</sup> W. | 67.58 feet |  |
| 7"  | Sugar Maple | S.85 <sup>o</sup> W. | 67.45 feet |  |
| 5"  | Aspen       | S.54 <sup>o</sup> W. | 73.68 feet |  |
| 6'  | Steel rail  | West                 | 61.84 feet |  |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_


SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Richard L. Drahn DATE 12-28-92

U.S.F.S. #A-13



SURVEYOR'S MICHIGAN REGISTRATION NO. 21564