

**SURVEY & REMONUMENTATION**

NOV 12 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
9<sup>th</sup> day of OCTOBER  
A. D. 1997 at 11:00 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
page 239  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey	Section 3	T <u>46N</u> R <u>42W</u>	H3
		T <u>    </u> R <u>    </u>	<u>    </u>
		T <u>    </u> R <u>    </u>	<u>    </u>
		T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

The one quarter section corner common to sections 3 and 10, T46N, R42W.

I, John R. Garske, in a field survey on July, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner set by A. Merryweather, D.S. in 1851.  
Original Bearing trees:  
A Lynn 14"-N36W 15 links  
A Cedar 12"-S41E 17 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found 1" dia. axle rod approximately 210' east of ~~South~~ East Shore Road. A blue line runs, north, south and east from this corner position which was pointed out to me by Don Holmes, Champion Timberlands Forester. Gogebic County Road Commission plans dated 1933 show this corner position monumented. This corner location has been used and accepted for over 50 years as being in the correct location with no disputes and I am accepting it as the 1/4 corner.

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the axle rod and set a 30" long x 2 1/2" dia. aluim. pipe monument with a 3 1/4" stamped alum. cap from which I established the following:

7" Hard Maple	North	15.27 feet
20" Hard Maple	S58°E	7.05 feet
20" Hard Maple	S62°W	24.99 feet
5" Hard Maple	N62°W	14.23 feet
6" Steel Sign rail	S16°W	1.20 feet

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

PEER GROUP APPROVED  
Richard L. Dahn 10/8/97  
COUNTY REPRESENTATIVE

Date

