

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
16TH day of DECEMBER
 A. D. 1993 at 2:25 o'clock
9 m., and recorded in
 Liber 4 of CORNERS
 on page 295
Betty Saari
 Register of Deeds

For corners in Gogebic (County) Located in: _____ Corner Code # _____

1. Public Land Survey Section 35 T 47N R 42W _____ I-13
 T _____ R _____
 T _____ R _____
 T 46N R 42W _____ I-1

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
Section corner common to S-34, 35, 3 & 2, T47N, R42W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on June 22, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by William A. Burt, U.S.D.S., August 9, 1848. Set cedar post from which a 10" hemlock bears N52°E, 15 links and a 14" lynn (basswood) bears N52°W, 56 links. No evidence found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" solid iron rod at corner position - found 14" maple blazed - S35°W - 16.05 feet; 8" ash - N40°W - 7.50 feet and a 1/2" iron rod capped RLS 17610 - due west - 7.15 feet. The iron rod as found has been used and accepted in several surveys of record for over 30 years.

PEER GROUP APPROVED
Richard P. Drahn 1/20/94
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On November 4, 1993, replaced found 1 1/2" solid iron rod with a standard aluminum County Monument - cap is stamped: County Remonumentation; T47N, R42W; S-34; S-35; S-3; S-2; T46N; 1993; RLS 28410. T46N; Established the following bearing trees and/or reference objects:

- 14" maple - S35°W - 16.05 feet
- 8" ash - N40°W - 7.50 feet
- 2" maple - S50°E - 4.62 feet
- Steel sign post - NE'ly - 1.42 feet



Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 12/9/93