

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
9th day of OCTOBER

A. D. 1997 at 11:00 o'clock

A m., and recorded in
Liber 6 of CORNERS

on page 240
Ramona Collins, Deputy
Register of Deeds

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey	Section 3	T <u>46</u> N	R <u>42</u> W	I-2
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

The one quarter section corner common to sections 2 and 3, T46N, R42W.

I, John R. Garske, in a field survey on July, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3	●	2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner set by A. Merryweather, D.S. in 1851.
Original Bearing trees:
Hemlock 8" - East - 5links
Sugar 24" - S85W - 7links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1" dia. drill steel at the corner position pointed out to me by Don Holmes, Forester for Champion Timberlands. This corner position is noted in old corner information by Kimberly Clark, predecessor to Champion. 1933 Gogebic County Road Commission plans for East Shore Rd. show the corner at 61 Links (40.26') west of centerline which checks with the existing centerline of the road. This corner has been used and accepted in many surveys for record and lies in harmony with landowners.

(Research on file)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PEER GROUP APPROVED
Richard R. Drabin 10/8/97
COUNTY REPRESENTATIVE

I replaced the drill steel with a 2 1/2" dia. alum pipe monument with a 3 1/4" dia. alum. cap stamped to identify the corner, from which I established the following:

13" ash	N25°E	10.86 feet(existing)
6" ash	S10°E	11.95 feet (existing)
7" ash	S60°W	19.27 feet (existing)
6' steel sign rail	S22°W	1.45 feet

Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date _____

