Register's Office LAND CORNER RECORDATION CERTIFICATE Gogebic County Received for record the 26 day of Tanuars Filing Requirement of Act 74, Mich. P.A. 1970 For corners in Gogebic Located In: Corner Code ## A. D. 1995 at 10:55 n'clock (County) A m., and recorded in 1. Public Land SurveySection 36 T 47N R 42W Liber 5 O[CORNERS R 00 page 182 46 N. R 42W. Ramona Collins Departe **Property Controlling** Register of Deads R in Section Miscellaneous R Register of Deeds Stamp & File Number Property in Sec. R , Recorded Plat. 4. Lot No. 5. Private Claims _ 1/4 corner to Sections 1 and 36, T47-46N, R42W I, John R. Garske, in a field survey on November 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below: 10 NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner by William Burt, Deputy Surveyor, August 6, 1847. Original bearing trees:

Cedar 8" - N67°E - 4 links Hemlock 14" - N37°W - 79 links Cedar 8" - N67°E - 4 links

1981 - Richard Drahn, RLS 21564, set a 2" I.D. x 4 ft. long iron pipe with a 3" diameter brass cap stamped to identify the corner. Bearing trees he established:

6" R. maple - N32°W - 48.10 feet 5" Y. birch - S03°W - 39.75 feet

8" hemlock - S82°E - 8.70 feet

Steel sign post - N76°W - 2.25 feet

Corner recorded 3/10/82, Liber 2, pg. 212.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the monument set by Dick Drahn in 1981 in good condition, the bearing trees are in good condition with the exception of the hemlock which is now a windfall. I established new accessories as noted below.

County record research on file with Register of Deeds.

PEER GROUP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 2" I.D. x 4 ft. long concrete filled galvanized iron pipe with a 3" diameter brass cap stamped: T46-47N, R42W; 1/4; S-1; S-36; RLS 21564, from which I established the following bearing trees and/or reference objects:

8" R. maple - N23°W - 28.11 feet

5" àsh - Ñ59°E - 27.11 feet

6" Y. birch - S07°W - 39.84 feet

Steel sign post - N69°W - 2.24 feet

28410 Surveyor's Mighigan License No.

JOHN R GARSKE LAND SURVEYOR

> SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

Fed. No. Z-23