

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

For corners in

Gogebic
(County)

Located In:

Corner Code --#

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 46N R 44W | M-4 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T 46N R 43W | A-4 |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

Received for record the
14TH day of MAY

A. D. 1998 at 3:10 o'clock

P m., and recorded in

Liber 6 of CORNERS

on page 353

Famona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 12 & 7; T.46 N., R.43-44 W.

I, Richard L. Drahn in a field survey on April 9, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/9/1847. Original B.T.s --- Y. Birch 18" S.70 E. 30 links (19.80')--- Y. Birch 12" N.53 W. 13 links (8.58') ---

Corner position re-established by Richard L. Drahn (21564) on 11/1/82 by single proportionate methods. He set a 2" X 30" aluminum pipe with a 3 $\frac{1}{4}$ " stamped aluminum cap and the following new B.T.s:

- | | | | |
|----|-----------------|---------|--------|
| 8" | Twin White Ash | N.55 E. | 42.09' |
| 4" | Sugar Maple | S.29 E. | 28.79' |
| 5" | Sugar Maple | S.54 W. | 12.89' |
| 6' | Steel sign rail | S.01 E. | 1.8' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County, Liber 2, Page 410 on 3/15/83.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- | | | | | |
|-----|-----------------|---------|--------|------------|
| 11" | Twin White Ash | N.52 E. | 41.84' | (new nail) |
| 7" | Sugar Maple | S.30 E. | 28.81' | |
| 8" | Sugar Maple | S.54 W. | 12.91' | |
| 6' | Steel sign rail | South | 1.75' | |

No evidence remains of the original corner or bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- | | | | |
|----|-----------|---------|--------|
| 5" | Red Maple | S.03 W. | 26.40' |
|----|-----------|---------|--------|

BEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date April 12, 1998

Surveyor's Michigan License No. 21564