

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

SECTION

For corners in

Gogebic
(County)

Located In: Corner Code #

- 1. Public Land Survey T46N R 44W M-6
T R
T R
T46N R 43W A-6
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

Received for record the
14th day of MAY
A. D. 1998 at 3:10 o'clock
P m., and recorded in
Liber 6 of CORNER
on page 355
Tamara Collins Depata
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 Corner 13 & 18; T.46 N., R.43-44 W.

I, Richard L. Drahn in a field survey on May 6, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/9/1847. Original B.T.s --- Y. Birch 12" N.41 1/2 E. 30 links (19.80') --- Spruce 12" S.41 1/2 W. 27 links (17.82') --- Corner re-established by Richard L. Drahn (21564) on 11/29/82 by single proportionate methods. He set a 3/4" X 4' long aluminum rod with a 3 1/4" stamped aluminum cap and the following new bearing trees:

- 11" Tamarack N.02 E. 83.04'
- 14" Tamarack N.57 E. 82.79'
- 7" Cedar S.21 W. 58.68'
- 6' Steel sign rail N.55 W. 1.96'

Corner recorded in Gogebic County Liber 2, Page 414 on 3/15/83.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- 13" Tamarack N.02 E. 83.03'
- 17" Tamarack N.56 E. 82.81'
- 9" Cedar S.24 W. 58.67'
- 6" Steel sign rail N.53 W. 1.90'

No evidence remains of the original corner or bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- 5" Black Ash N.70 W. 17.96'

FEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REGISTER



Signed by Richard L. Drahn Date May 10, 1998

Surveyor's Michigan License No. 21564