

**SURVEY & REMONUMENTATION**

SEP 08 1998

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

Gogebic  
 (County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>46N</u> R <u>44W</u> | <u>M-7</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T <u>46N</u> R <u>43W</u> | <u>A-7</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner 13, 24, 18 & 19: T.46 N., R.43-44 W.

I, Richard L. Drahn a field surveyor on May 6, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt on 8/9/1847. Original B.T.s --- 8" Tamarack S.66 W. 15 links (9.90') --- 8" Spruce N.50 E. 17 links (11.22') --- 6" Cedar S.58 E. 10 links (6.60') --- 8" Tamarack N.15 W. 28 links (18.48') --- Corner restored by Richard L. Drahn (21564) on 5/27/82 from the remains of the last three B.T.S; the fourth one still scribed. He set a 2" X 4' iron pipe with a 3" stamped brass cap and the following new B.T.S:

6"	Cedar	N.25 W.	11.25'
5"	Tamarack	N.86 E.	48.51'
5"	Black Spruce	S.20 W.	32.30'
6'	Steel sign rail	S.60 E.	1.6'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Corner recorded in Gogebic County Liber 2, Page 416 on 3/15/83.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

8"	Cedar	N.21 W.	11.24'
7"	Tamarack	N.86 E.	48.47'
6"	Black Spruce	S.22 E.	dead and down
6'	Steel sign rail	S.62 E.	1.56'

A depression remains from the second original B.T. and a very badly decayed tamarack stump still remains from the fourth B.T.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

New bearing tree referenced:

7"	Black Spruce	S.02 E.	2.57'
----	--------------	---------	-------

**PEER GROUP APPROVED**  
*Richard L. Drahn* 5/13/98  
 COUNTY REGISTER

Register's Office }  
 Gogebic County } ss.

Received for record the  
14<sup>th</sup> day of MAY  
 A. D. 19 98 at 3:10 o'clock  
P m., and recorded in  
 Liber 6 of CORNERS  
 on page 356  
*Romana Collins Deputy*  
 Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Richard L. Drahn Date May 10, 1998

Surveyor's Michigan License No. 21564