

SURVEY & REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

For corners in SECTION

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R43W	B-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Received for record the
18th day of JUNE
A. D. 1998 at 1:15 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 399
Ramona L. Collem, Dep.
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner, Sections 6 & 7, T46N, R43W

I, John P. Goss, in a field survey on May 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on September 10, 1851.

Original bearing trees: Cedar 6" S 13° E 19 links (12.54')
Cedar 12" N 09° W 34 links (22.44')

Richard L. Drahn, RLS, USFS, on June 13, 1984, restored corner position by retracement methods between G.L.O. section corners east and west. He set a 2" I.D. aluminum monument with 3/4" aluminum cap, stamped to indicated the corner position. He established the following reference objects:

8" Red Maple North 19.55' 8" Cedar S 71° E 9.78'
8" Cedar S 72° W 15.49' 6' steel sign post S 83° E 1.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 593 of Land Corners for Gogebic County. No original evidence found.

Found Richard L. Drahn, monument and witnesses.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard L. Drahn 6/17/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found 2" I.D. aluminum monument with 3/4" aluminum cap, with magnet stamped to read: T.46 N., R.43 W.; 1/4; S-6, S-7; 1984; R.L.S. 21564; from which I established existing and new reference objects:

11" Red Maple North 19.59'
10" Cedar S 71° E 9.75' new nail
11" Cedar S 72° W 15.45' new nail
6" Red Maple N 55° W 30.72'
6' steel sign post S 83° E 1.6' to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 26, 1998

USFS No. E-3