

**SURVEY & REMONUMENTATION**

SEP 08 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
14<sup>th</sup> day of MAY  
A. D. 1998 at 3:00 o'clock  
P m., and recorded in  
Liber 6 of CORNERS  
on page 333  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey

T46NR43W

B-5

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1/4 corner comm. to sec's. 7 & 18, T46N, R43W

I, John P. Goss, in a field survey on May 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5	●											
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on September 9, 1851.

Original bearing trees: Sugar 14" S 40° E 22 links (14.52')  
Sugar 12" N 34° W 20 links (13.20')

Richard L. Drahn, RLS, restored this corner from the remains of the two original bearing trees, on May 22, 1984. He set a 2" I.D. by 4' gal. iron pipe with 3" brass cap stamped to indicated the corner position. He established the following reference objects:

14" Sugar Maple N 47° W 25.45' 8" Sugar Maple S 51° W 44.72'  
10" Sugar Maple S 56° E 19.75' 6' steel sign post N 50° E 1.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
He record said corner in Liber 2, page 595 of Land Corners for Gogebic County.

Found Richard L. Drahn, monument and witnesses.

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

**VEER GROUP APPROVED**  
Richard L. Drahn 5/13/98  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found 2" I.D. gal. iron pipe with 3" brass cap which reads: T.46 N., R.43 W.; 1/4; S-7, S-18; 1984; R.L.S. 21564: from which I established the following existing and new reference objects:

19" Sugar Maple N 47° W 25.45 feet  
14" Sugar Maple S 56° E 19.75 feet  
11" Sugar Maple S 51° W 44.72 feet  
6' steel sign post N 50° E 1.7 feet (to face)  
6" Sugar Maple N 15° W 14.47 feet

( All measurement to nail in side of tree)

Signed by John P. Goss  
Surveyor's Michigan License No. 23509  
Fed. No. J-3

Date May 4, 1998

