

SURVEY &
REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R43W	B-9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register's Office }
Gogebic County } ss.

Received for record the
18TH day of JUNE
A. D. 1998 at 1:15 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 400
Ramona L. Collins, Dep
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner, Sections 19 & 30, T46N, R43W

I, John P. Goss, in a field survey on June 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

PEER GROUP APPROVED
Richard L. Drahn 6/18/98
COURT RECORDED

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, on September 11, 1851.
Original bearing trees: Y. Birch 7" S 37° E 17 links (11.22')
Sugar 10" N 48° W 19 links (12.54')

Richard L. Drahn, RLS, USFS, on October 11, 1984, restored corner position at record bearing and distance from the remains of the two original bearing trees. Both at that time stump holes. Corner position verified by retracement measurement and natural feature ties. He set a 2" I.D. aluminum monument with cast aluminum cap with magnet, stamped to indicated the corner position. He established the following reference objects: 7" Sugar Maple - N 18° E - 33.33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

8" Black Ash - S 03° E - 34.37' ; 6" Red Maple - S 58° W - 17.32'
6' steel sign post - N 57° E 1.98'

He recorded said corner in Liber 2, page 623 of Land Corners for Gogebic County. No original evidence found.

Found Richard L. Drahn, monument and witnesses.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found 2" I.D. aluminum monument with cast aluminum cap with magnet, stamped to read: T.46 N., R.43 W.; 1/4; S-19, S-30; 1984; R.L.S. 21564: from which I established existing and new reference objects:

8" Sugar Maple	N 18° E	33.33'	new nail
9" Black Ash	S 03° E	34.37'	
8" Red Maple	S 58° W	17.32'	new nail
6" Maple	N 08° W	20.75'	
6' steel sign post	N 57° E	1.98'	to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date June 6, 1998

USFS No. R-3