

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|------------|
| 1. Public Land Survey | T <u>46</u> N R <u>43</u> W | <u>G-4</u> |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |

Received for record the
18th day of JUNE
A. D. 1998 at 1:15 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 402
Normana L. Collins, Dep.
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner, Sections 7 & 8, T46N, R43W

I, John P. Goss, in a field survey on May 15, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, on August 26, 1851.
Original bearing trees: Lynn 10" S 20° E 4 links (2.64')
Sugar 20" N 44° W 13 links (8.58')

Richard L. Drahn, RLS, USFS, on June 13, 1984, restored corner position at record bearing and distance from the stump hole of the Lynn bearing tree, and to other section corners. He set a 2" I.D. aluminum monument with 3/4" aluminum cap, stamped to indicated corner position. He established the following references:

8" Sugar Maple N 65° E 13.30' 7" Sugar Maple S 37° E 25.96'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

9" Sugar Maple S 81° W 34.66' 6' steel sign post S 62° E 2.0'
He recorded said corner in liber 2, page 599 of Land Corners for Gogebic County

No original evidence found.

Found Richard L. Drahn, monument and witnesses.

I updated the monuments and accessories as noted below to state and county specification.

Act 74 research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2" I.D. aluminum monument with 3/4" aluminum cap which reads: T.46 N., R.43 W.; 1/4; S-7, S-8; R.L.S. 21564; 1984: from which I established the following existing and new reference objects:

- | | | |
|--------------------|---------|----------------|
| 10" Sugar Maple | N 65° E | 13.30' |
| 9" Sugar Maple | S 37° E | 25.94' |
| 11" Sugar Maple | S 83° W | 34.66' |
| 11" Sugar Maple | N 65° W | 25.65' |
| 6' steel sign post | S 62° E | 2.0' (to face) |

(All measurement taken to nail in side of tree)

Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 15, 1998

USFS. No. G-5

PEER GROUP APPROVED
Richard L. Drahn 6/17/98
COUNTY Gogebic

