

**SURVEY &
REMONUMENTATION**

SEP 08 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic County } ss.

For corners in

Gogebic

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>46</u> N <u>R43</u> W | <u>C-6</u> |
| | T___R___ | _____ |
| | T___R___ | _____ |
| | T___R___ | _____ |
| 2. Property Controlling
in Section | S___T___R___ | _____ |
| | S___T___R___ | _____ |
| 3. Miscellaneous
Property in Sec. | S___T___R___ | _____ |
| | S___T___R___ | _____ |

Received for record the
18th day of JUNE
A. D. 1998 at 1:15 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 403
Ramona L. Collins, Dep
Register of Deeds

Register of Deeds' Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner, Sections 17 and 18, T46N, R43W

I, John P. Goss, in a field survey on May 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18	●	17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 26, 1851.
Original bearing trees: Cedar 12" S 33° E 28 links (18.48')
Cedar 10" N 55° W 16 links (10.56')

Richard L. Drahn, RLS, USFS, on September 19, 1984, restored corner position at record bearing and distance from the remains of the two original bearing trees, and other recovered section corners. He set a 3/4" by 4' aluminum rod with 3 1/4" cast aluminum cap, stamped to indicated corner position. He established the following reference objects:
6" Cedar N 26° W 7.42'; 7" Cedar S 78° E 13.53'; 10" Cedar S 77° W 11.53'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6' steel sign post S 52° W 2.14'
He recorded said corner in Liber 2, page 625 of Land Corners for Gogebic County.
Found remains of Cedar stump 18".
Found Richard L. Drahn, monument and witnesses.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard L. Drahn 6/17/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 3/4" by 4' long Aluminum rod monument with 3 1/4" cast aluminum cap with magnet stamped to read: T.46 N., R.43 W.; 1/4; S-17, S-18; 1984; R.L.S. 21564: from which I established existing and new reference objects:

- | | | | |
|--------------------|---------|--------|----------|
| 8" Cedar | N 26° W | 7.33' | new nail |
| 10" Cedar | S 78° E | 13.51' | new nail |
| 14" Cedar | S 77° W | 11.55' | new nail |
| 6" Cedar | N 44° E | 13.30' | |
| 6' steel sign post | S 52° W | 2.14' | to face |

(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 26, 1998

USFS No. L-5