

**SURVEY &
REMONUMENTATION**

SEP 08 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }
Gogebic County } ss.

Received for record the
14TH day of MAY
A. D. 1998 at 3:00 o'clock
P m., and recorded in
Liber 6 of CORNERS
on page 335
Ramona Collins, Deputy
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T46NR 43W</u>	<u>C-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec:	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section corner, Sections 17, 18, 19, & 20, T46N, R43W

I, John P. Goss, in a field survey on May 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7		●										
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on July 17, 1851.
Original bearing trees: Sugar 8" S 45° E 6 links (3.96')
Sugar 10" N 68° W 21 links (13.86')

Richard L. Drahn, RLS, on September 19, 1984, restored corner position at record bearing and distance from the remains of the two original bearing trees. He set a 2" I.D. aluminum monument with 3/4" aluminum cap stamped to indicate the corner position. He established the following reference objects:

5" Sugar Maple N 26° W 17.61' 10" Y. Birch S 22° W 41.67'
5" Sugar Maple N 85° E 29.75' 6' steel sign post N 36° W 1.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2, page 627 of Land Corners for Gogebic County.

Found Richard L. Drahn, corner monument and witnesses.

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2" I.D. aluminum monument with 3/4" aluminum cap which reads: T.46 N., R. 43 W.; S-18, S-17, S-19, S-20; 1984; R.L.S. 21564: from which I established the following existing and new reference objects:

7" Sugar Maple N 26° W 17.60'
6" Sugar Maple N 85° E 29.75'
11" Sugar Maple S 22° W 41.67'
12" Basswood S 20° E 29.31'
6' steel sign post N 36° W 1.95' (to face)

(All measurements are to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 6, 1998