

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>43W</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds
Gogebic County

Received for record the
12TH day of MAY
A. D. 1999 at 11:00 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 99
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Quarter Corner 29 & 30; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 17, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by Austin Burt on 8/26/1851. Original B.T.s --- Y. Birch 24" S.44 W. 26 links (17.16) --- Maple 8' N.38 E. 16 links (10.56')

Corner restored by Richard L. Drahn, RLS 21564 on 10/11/84 from the remains of the two original B.T.s, two recovered line trees and a natural feature. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s --- 7" Y. Birch N.57 W. 23.80' --- 4" Sugar Maple N.86 E. 31.74' --- 6" Sugar Maple S.40 W. 29.32' --- 6' steel sign post N.49 E. 1.60' ---

Corner recorded in Gogebic County Liber 2, Page 631 on 12/10/84.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Recovered the monument as described and the bearing trees as follows:
10" Yellow Birch N.56 W. 23.88' (new nail)
6" Sugar Maple N.84 E. 31.70'
9" Sugar Maple S.39 W. 29.33' (new nail)
6' Steel sign rail N.51 E. 1.58'

Corner research on file with Gogebic County records.
Only a stump hole and a depression remain from the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
New bearing tree referenced:
13" Red Maple S.17 E. 13.52'

FIELD GROUP APPROVED
Richard L. Drahn 5/11/99
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date April 21, 1999

Surveyor's Michigan License No. 21564