

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>43W</u>	<u>C-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office } ss.
Gogebic County }

Received for record the
12th day of MAY
A. D. 1999 at 11:00 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 101
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Quarter Corner 31 & 32; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 28, 19 99
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/26/1851. Original B.T.s --- Cedar
6" S.79 E. 15 links (9.90') --- Cedar 8" N.33 W. 44 links (29.04') ---
Corner position re-established by Richard L. Drahn, RLS 21564 on 6/22/92
by single proportionate methods. He set a 3/4" X 4' aluminum rod with a
3 1/4" stamped aluminum cap. At a point on the section line S.00-05-41.5 E,
115.00' he set a Witness Corner comprised of a 3/4" X 3' aluminum rod with
a 3 1/4" stamped aluminum cap. The W.C. is witnessed by the following new
B.T.s ---10" Red Maple N.70 W. 29.18' --- 9" Hemlock S.81 E. 40.69' ---
9" Cedar S.19 W. 29.37' --- 6' Metal sign rail N.20 W. 1.78' ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County Liber 4, Page 169 on 10/8/92.

Due to flooding, I was unable to access the corners location. I recovered
the Witness Corner as described and the bearing trees as follows:

11"	Red Maple	N.72 W.	29.12'
9"	Hemlock	S.81 E.	40.69'
9"	Cedar	S.19 W.	29.28' (new nail)
6'	Steel sign rail	N,20 W.	1.78'

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the Witness Corner I referenced the following new B.T.:

5"	Sugar Maple	S.31 E.	51.16'
----	-------------	---------	--------

Richard L. Drahn 5/11/99
Surveyor



Signed by Richard L. Drahn

Date May 2, 1999

Surveyor's Michigan License No. 21564