

SURVEY &  
REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey

T46NR 43W D-9

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 corner comm. to sec's. 20 & 29, T46N, R43W

I, John P. GOSS, in a field survey on May 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on September 11, 1851.

Original bearing trees: Fir 8" S 58° E 17 links (11.22')  
Hemlock 20" N 70° W 18 links (11.88')

Richard L. Drahn, RLS, on October 30, 1984, restored corner position at record bearing and distance from the remains of the hemlock bearing tree. He set a 2" I.D. aluminum monument with 3/4" aluminum cap stamped to indicate corner position. He established the following reference objects.

6" Red Maple N 35° W 6.36' 6" Red Maple S 52° E 19.01'  
8" Red Maple N 47° E 27.92' 6' steel sign post N 48° W 2.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner in Liber 2 page 637 of Land Corners for Gogebic County. Found Richard L. Drahn corner monument and witnesses.

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVAL  
Richard L. Drahn 5/13/98  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the 2" I. D. aluminum monument with 3/4" aluminum cap which reads: T.46 N., R.43 W.: 1/4; S-20, S-29; 1984; R.L.S. 21564: from which I established the following existing and new reference objects:

8" Red Maple N 35° W 6.38'  
10" Red Maple N 47° E 27.02'  
8" Red Maple S 52° E 19.01'  
9" Balsam S 02° W 7.86'  
6' Steel sign post N 48° W 2.0' (to face)

( All measurement to nail in side of tree )

Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date May 6, 1998

Fed. No. R-7

Register's Office }  
Gogebic County } ss.

Received for record the  
14<sup>th</sup> day of May  
A. D. 1998 at 3:00 o'clock  
P m., and recorded in  
Liber 6 of CORNERS  
on page 339  
Kamona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

