

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County ss.

Received for record the
12TH day of MAY
A. D. 1999 at 11:00 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 103
Ramona Collins Deputy
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>43W</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

Quarter Corner 29 & 32; T.46 N., R.43 W.

Richard L. Drahn in a field survey on April 20, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/16/1851. Original B.T.s --- Cedar 8" S.45 E. 30 links (19.80') --- Y. Birch 24" N.40 E. 29 links (19.14') --- Neil J. McKenna recovered the original corner position marked by an iron pipe at record bearing and distance from the original Cedar B.T. Corner monumented by Richard L. Drahn on 8/23/85 at the site of the iron pipe. He set a 2" X 36" iron pipe with a 3" stamped brass cap and the following new B.T.s --- 15" Sugar Maple N.08 W. 18.96' --- 7" Sugar Maple N.81 E. 29.19' --- 13" Sugar Maple S.50 W. 39.49' --- 6' metal post S.89 E. 2.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County Liber 2, Page 727 on 1/10/86.

Recovered the monument as described and the B.T.s as follows:

16"	Sugar Maple	N.14 W.	18.93'
9"	Sugar Maple	N.80 E.	29.11' (new nail)
15"	Sugar Maple	S.48 W.	39.48'
6'	Steel sign rail	N.88 E.	2.16'

Corner research on file with Gogebic County records.

No evidence remain of the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

6" Sugar Maple S.24 E. 29.93'

FIELD GROUP APPROVED
Richard L. Drahn 5/11/99
CORNER RE-ESTABLISHED



Signed by Richard L. Drahn Date April 21, 1999

Surveyor's Michigan License No. 21564