

SURVEY & REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
14TH day of MAY
A. D. 1998 at 3:00 o'clock
P m., and recorded in
Liber 6 of CORNERS

on page 340
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey		<u>T46NR 43W</u>	<u>E-3</u>
		T___R___	_____
		T___R___	_____
		T___R___	_____
2. Property Controlling in Section	S___	T___R___	_____
	S___	T___R___	_____
3. Miscellaneous Property in Sec.	S___	T___R___	_____
	S___	T___R___	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner, Section 4, 5, 8 & 9, T46N, R43W.

I, John P. Goss, in a field survey on May 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3				●								
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 27, 1851.

Original bearing trees: Y. Birch 18" S 64°E 4 links (2.64 feet)
Sugar 12" N 64°W 32 links (21.12 feet)

Richard L. Drahn, RLS, restored corner position by retracement measurements North, South, East and West to recovered natural feature ties. He set a 2" I.D. by 30" Aluminum monument with 3/4" aluminum cap to indicated position: He established the following references: 3" Aspen - N 73° W - 28.06'; 7" Aspen - N 03° W - 27.71'; 6" Balsam - N 45° E - 30.47'; 5/8" x 16" iron pipe - S 01° E - 9.55'; 6" steel sign post - N 08° E - 2.5'. On July 25, 1984.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No original evidence exists due to road construction.

Found Richard L. Drahn corner monument and witnesses.

I updated the corner monument and accessories as noted below to state and county specification.

Act 74 research on file.

Drahn recorded this corner in Liber 2, page 603 of LCGC.

PEER GROUP APPROVED
Richard L. Drahn 5/13/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found 2" I.D. aluminum monument with 3/4" aluminum cap stamped to read: T.46 N., R.43 W., S-4, S-5, S-8, S-9; 1984; R.L.S. 21564: from which I established existing and new bearing trees and reference objects.

- 9" Aspen N 73° W 28.06'
- 7" Aspen(stump) N 03° E 27.71'
- 5/8" x 16" iron pipe S 01° E 9.55'
- 6" steel sign post N 08° E 2.5' (to face)
- 6" Balsam N 24° W 34.45'
- 9" Spruce N 63° E 25.81'

(All measurement to trees are to nail in side of tree)

Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 2, 1998



Fed. No. E-9