

**SURVEY &
REMONUMENTATION**

OCT 03 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in	Gogebic	Located In:	Corner Code #
	(County)		
1. Public Land Survey	T 46N R 43W	E-8	
	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register's Office }
Gogebic County } ss.

Received for record the
10TH day of JUNE
A. D. 1996 at 9:30 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 348
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

One-quarter corner common to Sections 20 and 21, T46N, R43W

I, John R. Garske, in a field survey on May 29, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- In 1851 Austin Burt set a post at 40.25 chs. from which a 8" Y. birch bears S27°E - 7 links and a 18" cedar - N34°W - 30 links.
- 1985 Plat of Survey - Sectional breakdown of Section 20 by Richard Drahn, RLS 21564 and corner certificate recorded Jan. 10, 1986, Liber 2, Page 728., set a 2" I.D. x 12" long concrete filled galvanized iron pipe, capped with a 3" brass tablet stamped: T46N, R43W; 1/4; S-20; S-21; 1985; RLS 21564, from which a P. Pole #21 - 2-8/94 bears N68°E - 46.64 feet and a steel "Do Not Pass" sign - N51°W - 6.22 feet; a steel "No Passing" sign - N76°W - 48.76 feet and brass capped reference monument stamped: T46N, R43W; 1/4' R.M., S-20; S-21; RLS 21564; 1985; West - 26.16 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 3" diameter brass cap one foot below road (M-64) East shoulder, stamped as noted above. Also found reference monument as noted above. All other reference objects had been obliterated.

I updated the corner to county specifications as noted below.

(Research on file)

PEER GROUP APPROVED
Richard L. Drahn 6/6/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The corner position is marked by a 3" diameter brass cap and a brass capped reference monument as noted above. I established the following bearing trees and/or reference objects:

- P. Pole #21-2-3-05/03 - S67°E - 46.66 feet
- 6" R. maple - S72°W - 121.96 feet
- 10" B. ash - N36°W - 147.00 feet
- Reference Monument - East - 26.16 feet with steel rail and sign - N77°E - 2.30 feet



Signed by John R. Garske
Surveyor's Michigan License No. 28410

Date 6/6/96