

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic (County) Located In: Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>43W</u>	<u>E-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's office }  
Gogebic County } ss.

Received for record the  
12<sup>th</sup> day of MAY  
A. D. 19 99 at 10:55 o'clock  
9 a.m., and recorded in  
Liber 7 of CORNERS  
on page 105  
Ramona L. Collins Deput  
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Quarter Corner 28 & 29; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 20, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/27/1851. Original B.T.s --- Cedar 10" S.73 E. 24 links (15.84') --- Spruce 10" N.52 W. 34 links (22.44') ---  
Corner restored by Richard L. Drahn, RLS 21564 on 6/30/92 by proportionate methods. He set a 2" X 30" aluminum pipe with a 3 1/2" stamped aluminum cap and the following new B.T.s: ---10" Twin Cedar N.27 W. 15.01' --- 10" Black Spruce S.60 E. 19.41' --- 8" Cedar S16 W. 29.83' --- 6' metal sign rail N.54 E. 1.42' ---

Corner recorded in Gogebic County Liber 4, Page 170 on 7/8/92.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

10"	Twin Cedar	N.29 W.	14.99'
10"	downed Black Spruce	S.61 E.	-----
9"	Cedar	S.16 W.	29.80'
6'	Steel sign rail	N.51 E.	1.41'

No evidence of the original B.T.s recovered.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

5"	Cedar	S.76 E.	22.41'
----	-------	---------	--------

BEEN GROUP  
Richard L. Drahn 5/11/99  
COUNTY REGISTER



Signed by Richard L. Drahn Date April 21, 1999

Surveyor's Michigan License No. 21564