

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.  
Gogebic County }

SECTION

For corners in

Received for record the  
12<sup>TH</sup> day of MAY  
A. D. 1999 at 10:55 o'clock  
A m., and recorded in  
Liber 7 of CORNERS  
on page 107  
Ramona Collins DePute  
Register of Deeds

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>43W</u>	<u>E-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Quarter Corner 32 & 33; T.46 N., R.43 W

I, Richard L. Drahn in a field survey on April 27, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/27/1851. Original B.T.s --- Hemlock 14" West 4 links (2.64') --- Ironwood 7" East 32 links (21.12') --- Corner position re-established by Richard L. Drahn, RLS 21564 on 7/9/92 by single proportionate methods. He set a 2 1/4" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s --- 6" Sugar Maple N.35 E. 19.74' --- 10" Sugar Maple S.87 E. 20.82' --- 8" Sugar Maple S.03 E. 38.96' --- 6' metal sign rail N.58 W. 1.85' ---

Corner recorded in Gogebic County Liber 4, Page 172 on 10/8/92.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows;  
7" Sugar Maple N.38 W. 19.87'  
10" Sugar Maple S.87 E. 20.82'  
8" Sugar Maple S.05 E. 38.97'  
6' Steel sign rail N.87 W. 1.84'

Corner research on file with Gogebic County records.

No GLO evidence recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

8" Black Cherry S.89 W. 34.89'

Richard L. Drahn 5/11/99  
Surveyor



Signed by Richard L. Drahn

Date April 29, 1999

Surveyor's Michigan License No. 21564