

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic Located In: Corner Code #  
(County)

1. Public Land Survey T 46N R 43W F-11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register's Office }  
Gogebic } ss.

Received for record the  
12<sup>th</sup> day of MAY  
A. D. 1999 at 10:55 o'clock  
A m., and recorded in  
Liber 7 of CORNERS  
on page 109  
Pamona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Quarter Corner 28 & 33; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 26, \_\_\_\_\_, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/16/1851. Original B.T.s --- Sugar 6" S.35 W. 14 links (9.24') --- Y. Birch 20" N.52 E. 11 links (7.26') ---

Corner position restored by Richard L. Drahn, RLS 21564 on 5/5/92 from the remains of the two original B.T.s. He set a 2½" X 30" aluminum pipe with a 3½" stamped aluminum cap and the following new B.T.s --- Sugar Maple 6" N.21 E. 16.78' --- 5" Sugar Maple S.82 E. 35.56' --- Red Maple 10" S.03 W. 13.57' --- 6' Metal sign rail S.85 W. 2.36' ---

Corner recorded in Gogebic County Liber 4, Page 173 on 10/8/92.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

7"	Sugar Maple	N.18 E.	16.75'
6"	Sugar Maple	S.82 E.	35.55'
11"	Red Maple	S.05 W.	13.63'
6'	Steel sign rail	S.82 W.	2.38'

A series of root holes still remains from the original Sugar B.T. A series of root holes with fragments of Y. Birch bark remains from the original Yellow Birch B.T.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

5" Sugar Maple N.50 W. 14.88'

Richard L. Drahn 5/11/99  
Surveyor



Signed by Richard L. Drahn

Date April 29, 1999

Surveyor's Michigan License No. 21564