

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
12TH day of MAY
A. D. 1999 at 10:55 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 110
Ramona Collins DePuy
Register of Deeds

For corners in SECTION
Gogebic
(County)

Located in: Corner Code #

1. Public Land Survey

T 46N R 43W F-13
T _____ R _____
T 45N R 43W F-1

2. Property Controlling
in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____
S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Quarter Corner, 33 & 4; T.45-46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 17, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/5/1847. Original B.T.s --- Hemlock 8" N.10½ E. 54 links (35.64') --- Y. Birch 14" N.30½ W. 43 links (28.38') --- Corner restored by Richard L. Drahn, RLS 21564 on 5/12/92 from the remains of the two original B.T.s. He set a 2½" X 30" aluminum pipe with a 3¼" stamped aluminum cap and the following new B.T.s --- 8" Aspen N.57 W. 27.63' --- 7" Aspen N.12 E. 40.87' --- 8" Aspen S.17 W. 6.3' --- 6' metal sign rail S.03 W. 2.22' ---

Corner recorded in Gogebic County Liber 4, Page 174 on 10/8/92.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

9"	Aspen	N.56 W.	27.56'	(new nail)
8"	Aspen	N.15 E.	40.89'	(new nail)
10"	Aspen	S.17 W.	6.12'	(new nail)
6'	Steel sign rail	S.02 W.	2.21'	

Corner research on file with Gogebic County records.

Only depressions remain from the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

13"	Aspen	N.76 W.	12.47'
6'	Steel fence rail	North	0.37'

Richard L. Drahn 5/11/99
COUNTY REGISTER



Signed by Richard L. Drahn

Date April 21, 1999

Surveyor's Michigan License No. 21564