

SURVEY &
REMONUMENTATION

DEC 15 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|------------|
| 1. Public Land Survey | T <u>46</u> W R <u>43</u> W | <u>G-6</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Received for record the
25TH day of NOVEMBER
A. D. 1998 at 10:00 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 84;

Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 cor. comm. to sec's. 15 & 16, T46N, R43W

I, John P. Goss, in a field survey on Nov. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on August 30, 1851.
Original bearing trees: Fir 10" S 60° E 14 links (9.24')
Fir 10" N 29° W 22 links (14.52')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found wood stake at corner position.
Restored corner position at record bearing and distance from badly decayed Fir windfall at S 60° E. Corner position verified by retracement measurement South 469 feet to a 14" to 18" badly decayed Cedar stump, also to other natural feature ties.

Act 74 research on file.

DEED GROUP APPROVED
Richard P. Drazalm 11/24/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a ~~5/8~~ ^{3/4} inch by 48 inch aluminum marsh rod with 3/4 inch aluminum cap stamped to read: County Remonumentation; T.46 N., R.43 W., 1/4; S-15, S-16; 1998; P.S. 23509. I established the following bearing trees and referenda object.

Nail in 7" Balsam S 12° W 14.01'
Nail in 6" Balsam N 86° E 11.03'
Nail in 5" Balsam N 42° W 9.51'
6" rail & sign S 65° E 1.92' to face



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date November 4, 1998