

SURVEY &
REMONUMENTATION

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T.46NR 43W	G-9
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

Received for record the
18th day of JUNE
A. D. 1998 at 1:15 o'clock
P m., and recorded in
Liber 6 of CORNERS
page 407
Ramona L. Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

Section Corner, Sections 21, 22, 27 & 28,

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

T.46 N., R.43 W.

I, John P. Goss, in a field survey on May 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on August 28, 1851.
Original bearing trees: Hemlock 8" S 77° W 43 links (28.38')
Y. Birch 12" N 77° E 34 links (22.44')

Richard L. Drahn, RLS, USFS, on September 27, 1984, restored corner position at record bearing and distance from the remains of the two original bearing tree and with other line calls. He set a 2" I.D. concrete filled galv. pipe with capped a 3" circular brass tablet stamped to indicated the corner's position. He established the following reference objects:
14" Hemlock - N 12° E - 44.91'; 10" Hemlock - S 35° E - 14.99'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10" Sugar Maple - S 68° W - 28.83'; 6' steel sign post - N 52° E - 1.95'
He recorded said corner in Liber 2, page 641 of Land Corners for Gogebic County.
Found Hemlock stump hole S 77° W - 43 links (28.4')
Found Richard L. Drahn, monument and witnesses.

I updated the monument and accessories as noted below to state and county specification.

Act 74 research on file.

PEER GROUP APPROVAL
Richard L. Drahn 6/17/98
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found 2" I.D. concrete filled galv. pipe capped with a 3" circular brass tablet stamped to read: T.46 N., R.43 W.; S-21, S-22, S-27, S-28; 1984; R.L.S. 21564: from which I established the following existing and new reference objects:

15" Hemlock	N 12° E	44.91'	
11" Hemlock	S 35° E	14.99'	new nail
13" Sugar Maple	S 68° W	28.83'	new nail
10" Cedar	N 35° W	19.23'	
6' steel sign post	N 52° E	1.95'	to face

(All measurement taken to nail in side of tree)

Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 27, 1998

USFS No. R-13

