

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION
Gogebic (County)

Located In: Corner Code #
1. Public Land Survey T46N R 43W G-12
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

Register's Office }
Gogebic County } sa.

Received for record the
12TH day of MAY
A. D. 1999 at 10:55 o'clock
A. m., and recorded in
Liber 7 of CORNERS
on page 111
Ramona Collins-Oldroyd
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner, 33 & 34; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 26, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/28/1851. Original B.T.s --- Cedar 12" S.33 E. 11 links (7.26') --- Y. Birch 12" N.71 W. 20 links (13.20') --- C & NW Railroad plan (circa 1900) shows the corner laying 370.0' east of the centerline.

Corner position restored by Richard L. Drahn, RLS 21564 on 6/11/92 from the 1900s railroad tie and natural feature ties. He set a 2 1/2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s --- Aspen 5" N.16 W. 11.26' --- 11" Aspen N.33 E. 9.92' --- 6" Aspen N.33 E. 6.38' --- 6' metal sign rail N.77 W. 2.92' ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:
6" Aspen N.18 W. 11.25'
11" Aspen N.33 E. 9.89'
7" Aspen S.19 W. 6.38'
6' Steel sign rail N.76 W. 2.91'

No evidence of the original corner or bearing trees remains.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

5" Balsam N.78 W. 14.07'

Richard L. Drahn 5/11/99
COLLECTOR



Signed by Richard L. Drahn Date April 29, 1999

Surveyor's Michigan License No. 21564