

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located in:

Corner Code #

1. Public Land Survey

T46NR 43 G-13
T R

2. Property Controlling
in Section

T45NR 43W G-1
S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner 33, 34, 3 & 4; T.45-46 N., R.43 W.

Richard L. Drahn, in a field survey on April 26 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 8/5/1847. Original B.T.s --- Fir 8" N.44 W. 34 links (22.44') --- Y. Birch 12" N.56 E. 80 links (52.80') --- Spruce 16" S.25 E. 27 links (17.82') --- Cedar 12" S.55 W. 38 links (25.08')

Corner position restored by Donald D. Lappala, RLS 12585 on 6/14/66 from the remains of the 1st, 2nd and 4th original B.T.s and natural features north and west of the corner. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 12" Cedar N.56 W. 50.3' --- 7" Cedar N.41 E. 48.4' --- 9" Black Ash S.10 E. 5.3' ---

Corner recorded in Gogebic County USFS Liber, Page A-13 on 9/7/67.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

13"	Cedar	N.57 W.	49.95' (new nail)
9"	Cedar	N.43 E.	48.57' (new nail)
9"	Black Ash	S.09 E.	5.26' (new nail)

Only small fragments of Yellow Birch bark remains from the original B.T.s.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

6'	Steel sign rail	S.58 E.	2.68'
4"X4"X7'	Cedar sign post	S.57 W.	3.88'

Richard L. Drahn 5/11/99
SURVEYOR

Register's Office }
Gogebic County } ss.

Received for record the
12TH day of MAY
A. D. 1999 at 10:55 o'clock
A. m., and recorded in
Liber 7 of CORNERS
on page 112
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Richard L. Drahn
Surveyor's Michigan License No. 21564

Date May 2, 1999

USFS Z-13