

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.  
Gogebic County }

Received for record the

12<sup>th</sup> day of MAY

A. D. 1999 at 10:55 o'clock

A m., and recorded in

Liber 7 of CORNERS

on page 114

Ramona Collins Deputy  
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>43W</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Quarter Corner 22 & 27; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 24, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/16/1851. Original B.T.s --- Cedar 10" S.59 E. 14 links (9.24') --- Cedar 7" N.64 W. 14 links (9.24') ---

Corner restored by Richard L. Drahn, RLS 21564 on 9/27/84 from the remains of the two original B.T.s and from natural feature and line tree ties east and west. He set a 3/4" X 4' aluminum rod with a 3 1/4" stamped aluminum cap and the following new B.T.s : --- 9" Cedar N.58 W. 7.06' --- 7" Cedar N.27 E. 14.00' --- 6" Cedar S.58 E. 13.25' --- 6' Steel sign rail N.53 E. 1.9'---

Corner recorded in Gogebic County Liber 2, Page 645 on 12/10/84.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

11"	Cedar	N.58 W.	7.05'	(new nail)
8"	Cedar	N.26 E.	14.21'	(new nail)
7"	Cedar	S.61 E.	13.42'	(new nail)
6'	Steel sign rail	N.47 E.	2.12'	

No evidence of the original corner or B.T.s remains.

Corner research on file with Gogebic County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

9"	Cedar	S.38 W.	45.58'
----	-------	---------	--------

Richard L. Drahn 5/11/99  
Surveyor



Signed by Richard L. Drahn Date April 29, 1999

Surveyor's Michigan License No. 21564

USFS R-15