

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
10th day of JUNE
A. D. 1999 at 10:05 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 156
Pamela Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T46N R43W</u>	<u>1-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. , Recorded Plat
5. Private Claims
Section Corner 2, 3, 10 & 11; T.46 N., R.43 W.

I, Richard L. Drahn, in a field survey on May 19, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3								●				
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt on 9/5/1851. Original bearing trees:
W. Pine 8" S.54° W. 19 links (12.54')
W. Pine 10' N.67° E. 10 links (6.60')

Corner restored by Richard L. Drahn, RLS 21564 on 6/23/86 from the remains of the two original B.T.s and from natural feature ties north, south, east and west. He set a 2" X 2' iron pipe monument with a 3" stamped brass cap and the following new B.T.s:
White Spruce 12" S.10° E. 22.41'
White Spruce 7" S.75° W. 25.23'
Red Maple clump 4" N.33° E. 5.52'
Chiseled "X" in ledge N.03° W. 22.90'

The original W. Pine bearing tree at S.54 W. is now a decayed and burned White Pine stump. The B.T. at N.67 E. Has been reduced to a series of burned and decayed White Pine roots.

Corner recorded in Gogebic County Liber 3, Page 15 on 3/4/87.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I recovered the monument as described and the bearing trees as follows:
White Spruce 14" S.13° E. 22.16' (new nail)
White Spruce 10" S.76° W. 25.29' (new nail)
Red Maple clump 6" N.31° E. 5.50'
Chiseled "X" in ledge N.03° W. 22.89'

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:

White Spruce 4" S.74° E. 26.21'

PEER GROUP APPROVED

Richard L. Drahn 6/9/99
CORNER 2474452-41-325



Signed by Richard L. Drahn

Date May 23, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976

USFS E-17

REVISED JAN., 1983

REVISED OCT., 1995