

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }  
Gogebic County } ss.

Received for record the  
21<sup>ST</sup> day of JULY  
A. D. 1999 at 1:15 o'clock  
P m., and recorded in  
Liber 7 of CORNERS  
on page 183  
Ramona Collins Deputy  
Register of Deeds

SECTION  
For corners in

Code #	<u>Gogebic</u> (County)	Located In:	Corner
1. Public Land Survey		<u>T46N R43W</u>	<u>1-4</u>
		T ___ R ___	_____
		T ___ R ___	_____
		T ___ R ___	_____
2. Property Controlling in Section	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner 10 & 11; T.46 N., R.43 W.

I, Richard L. Drahn, in a field survey on June 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10	●	11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt 9/6/1851. Original bearing trees:

Cedar	14"	S.53° E.	8 links (5.28')
Cedar	7"	N.59° W.	20 links (13.20')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the remains of the bearing tree at N.59° W.. It is now a very badly decayed 12"-16" broken cedar stump. This is the only old growth Cedar stump recovered within a 30' radius. No evidence remains from the original bearing tree at S.53° E. Natural feature ties (swamp calls) north and south of the corner are in accordance with the field notes of the original Government survey.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree).

White Spruce	10"	N.18° W.	16.99'
Aspen	7"	S.48° W.	18.72'
Aspen	5'	S.75° E.	26.19'
Steel sign rail	6'	S.14° E.	2.11'

DEED GROUP APPROVED

Richard L. Drahn 7/20/99  
COUNTY REGISTER



Signed by Richard L. Drahn Date June 20, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971