

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
12th day of MAY
A. D. 1999 at 10:50 o'clock
7 m., and recorded in
Liber 7 of CORNERS
on page 117
Romona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>43W</u>	<u>I-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Quarter Corner 14 & 15; T.46 N., R.43 W.

Richard L. Drahn, in a field survey on April 8, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/6/1851. Original B.T.s ---Y. Birch 14" S.67 W. 10 links (6.60') --- Y. Birch 14" N.31 E. 36 links (23.76') ---
Corner restored by Richard L. Drahn, RLS 21564 on 6/25/86 from the remains of the first bearing tree and by retracement measurement north and south to recovered section corners.

He set a 2½" X 48" iron pipe with a 3" stamped brass cap and the following new bearing trees:

- 9" Sugar Maple N.32 W. 35.14'
- 5" Black Ash N.73 E. 24.32'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 7" Sugar Maple S.27 W. 12.67'
- 6' Steel sign rail S.53 E. 3.0'

Corner recorded in Gogebic County; Liber 3, Page 16 on 3/4/87.

Corner research on file with Gogebic County records.

Fragments of Y. Birch wood and bark @ S.67 W still remain from the original B.T. Recovered the monument as described and the bearing trees as follows:

- 10" Sugar Maple N.34 W. 35.10'
- 7" Black Ash N.72 E. 24.26'
- 9" Sugar Maple S.28 W. 12.69'
- 6' Steel sign rail S.54 E. 2.93'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- 4" White Ash S.36 E. 28.92'



PEER GROUP APPROVED
Richard L. Drahn 5/11/99
COUNTY APPROVED

Signed by Richard L. Drahn Date April 11, 1999
Surveyor's Michigan License No. 21564