

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R43W	I-10
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register's Office }
Gogebic County } ss.

Received for record the
10TH day of JUNE
A. D. 1999 at 10:05 o'clock
A m., and recorded in
Lib. 7 of CORNERS
on page 158
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 26 & 27; T.46 N., R.43 W.

I, Richard L. Drahn, in a field survey on June 8, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt on 9/4/1851. Original bearing trees:

Sugar Maple	12"	N.76° E.	49 links (32.34')
Sugar Maple	12"	West	17 links (11.22')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Corner position restored at record bearing and distance from the remains of the two original bearing trees. The first is a large series of root holes (species undetermined). The second one is now a large series of root holes with fragments of Sugar Maple wood. The 8.79 chain distance north to "Enter Tamarack swamp, ENE-SW", is in accordance with the field notes of the original Government survey.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing trees:

Sugar Maple	12"	S.03° E.	7.79'
Sugar Maple	8"	N.76° W.	18.74'
Sugar Maple	10"	N.43° E.	26.02'
Steel sign rail	6"	N.81° E.	1.63'

PEER GROUP APPROVED
Richard L. Drahn 6/9/99
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date June 9, 1999

Surveyor's Michigan License No. 21564
USFS T-17

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971

REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1986