

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office  
Gogebic County

Received for record the  
21<sup>ST</sup> day of JULY  
A. D. 1999 at 1:15 o'clock  
P. m., and recorded in  
Liber 7 of CORNERS  
on page 186  
Barbara Collins, Deputy  
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 46N R43W</u>	<u>1-13</u>
	<u>T R</u>	
	<u>T R</u>	
2. Property Controlling in Section	S <u>T R</u>	
	S <u>T R</u>	
3. Miscellaneous Property in Sec.	S <u>T R</u>	
	S <u>T R</u>	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner 34, 35, 2 & 3; T.45-46 N., R.43 W.

I, Richard L. Drahn, in a field survey on June 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 8/5/1847. Original bearing trees:

Cedar	10"	N.48° E.	29 links (19.14')
Cedar	12"	N.22° W.	30 links (19.80')
Cedar	8"	S.60° E.	4 links ( 2.64' )
Balsam	8"	S.30° W.	10 links ( 6.60' )

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the first two original bearing trees. The first consists of a portion of the Cedar root crown at N.48° W.. The second is now a downed, badly decayed 12"-16" Cedar windfall.. No evidence remains of the third and fourth bearing tree.

The 4.50 chain distance East to "Enter swamp, SSW" although indistinct, checks to timber type change.

An old 4" X 4" X 5' Cedar post bears S.71° E., 5.7'.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" x 4' aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

Cedar	7"	N.75° E.	29.28'
Black Ash	5"	N.65° W.	18.63'
Black Ash	6"	S.04° E.	11.09'
Steel sign rail	6"	North	1.43'

DEED GROUP APPROVED  
Richard L. Drahn 7/20/99  
COUNTY REGISTER



Signed by Richard L. Drahn Date June 20, 1999  
Surveyor's Michigan License No. 21564