

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
21st day of JULY
A. D. 1999 at 1:15 o'clock
P. m., and recorded in
Liber 7 of CORNERS

on page 107
Romona Collins Deputy
Register of Deeds

For corners in

Gogebic Located In: Corner Code #
1. Public Land Survey T.46N R.43W J-3
2. Property Controlling S. T. R.
3. Miscellaneous S. T. R.
Property in Sec. S. T. R.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Quarter Corner 2 & 11; T.46 N., R.43 W.

I, Richard L. Drahn, in a field survey on June 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at row 3, column I.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/5/1851. Original bearing trees:

Sugar 14" S.34 W. 14 links (9.24')
Sugar 10" N.20 E. 34 links (22.44')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a large stump hole. The second one is now a large Sugar Maple stump, decayed to ground line.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Sugar Maple 8" N.01 W. 23.55'
Yellow Birch 8" S.70 E. 19.43'
Sugar Maple 11" S.61 W. 17.55'
Steel sign rail 6" N.45 W. 1.54'

PEER GROUP APPROVED
Richard L. Drahn 7/20/99
COUNTY REGISTER



Signed by Richard L. Drahn Date July 20, 1999
Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1986