

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
12th day of MAY

A. D. 1999 at 10:45 o'clock
A m., and recorded in

Liber 7 of CORNERS
page 122

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 43W	J-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Quarter Corner 23 & 26; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 23, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/4/1851. Original B.T.s --- Hemlock 7" S.26 W. 27 links (17.82') --- Y. Birch 20" N.33 E. 51 links (33.66') --- J.W. Stoor, on 1/18/39 recovered the Hemlock B.T. still scribed, He set a cedar post and placed a location poster on a 16" Yellow Birch. Corner restored by Richard L. Drahn, RLS 21564 on 7/14/75 from the remains of the two original B.T.s. He recovered the 1939 post and location poster. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following: --- 8" Maple N.14 E. 20.0' --- 11" Maple N.46 E. 37.8' --- 6" Maple S.85 E. 20.4' --- 7' Metal sign rail North 2.2' --- Corner recorded in Gogebic County Liber 1, Page 149 on 1/27/76.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:
11" Sugar Maple N.14 E. 20.12' (new nail)
14" Sugar Maple N.46 E. 37.71' (new nail)
9" Sugar Maple S.85 E. 20.33' (new nail)
7' Steel sign rail N.06 E. 2.18'

The original Hemlock B.T. is now a decayed Hemlock stump and the Y. Birch is now a large depression.

Corner research on file with Gogebic County records

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

9" Sugar Maple S.88 W. 34.66'

Richard L. Drahn 5/11/99
COUNTY



Signed by Richard L. Drahn

Date April 29, 1999

Surveyor's Michigan License No. 21564