

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

For corners in

Gogebic
Code # _____
(County)

Located In:

Corner

1. Public Land Survey

T	<u>46N</u>	R	<u>43W</u>	K-1
T	_____	R	_____	_____
T	_____	R	_____	_____
T	<u>47N</u>	R	<u>43W</u>	K-13
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

2. Property Controlling in Section
3. Miscellaneous Property in Sec.

Received for record the
10TH day of JUNE
A. D. 1999 at 10:05 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 160
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 1, 2, 35 & 36; T.46-47 N., R.43 W.

I, Richard L. Drahn, in a field survey on May 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 8/7/1847. Original bearing trees:

Y. Birch	8"	N.70 °E.	87 links (57.42')
Y. Birch	10"	N.75° W.	57 links (37.62')
Y. Birch	10"	S.61° W.	22 links (14.52')
Y. Birch	10"	S.43° E.	23 links (15.18')

Corner restored by Richard L. Drahn, RLS 21564 on 6/9/86 from the stump holes of the 1st, 2nd, and 4th B.T.s and from the decayed stump of the 3rd B.T. and from retracement measurement east and south to natural feature ties and recovered corners. He set a 2" X 3' iron pipe monument with a 3" stamped brass cap and the following new B.T.s:

Red Maple	10"	S.66° E.	38.95'
Cherry	8"	S.12° E.	14.03'
Cherry	5"	S.88° W.	29.88'
Steel sign rail	6'	S.45° W.	2.4'

Corner recorded in Gogebic County Liber 3, Page 17, on 3/4/87.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the monument as described and the bearing trees as follows:

Red Maple	14"	S.67° E.	39.01' (new nail)
Black Cherry	10"	S.15° E.	13.42' (new nail)
Black Cherry	9"	S.86° W.	30.18' (new nail)
Steel sign rail	6'	S.47° W.	2.34'

Only depressions or stump holes remain from the original bearing trees.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:

Black Cherry 10" N.61° E. 28.38'



DEED GROUP APPROVED
Richard L. Drahn 6/9/99
COUNTY REGISTER

Signed by Richard L. Drahn Date May 21, 1999

Surveyor's Michigan License No. 21564