

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

Received for record the
12th day of MAY
A. D. 1999 at 10:45 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 125
Ramona Collins, Deput
Register of Deeds

SECTION
For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46</u> N R <u>43</u> W	<u>K-4</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 11 & 12; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 28, 1999 to hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11	●	12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/3/1851. Original B.T.s --- Fir 8" East 6 links (3.96') --- Cedar 14" West 44 links (29.04') ---
Paul R. Mack on 4/10/35 recovered the cedar bearing tree still scribed and placed a location poster on the SE side of the B.T.
Richard L. Drahn, RLS 21564 recovered the still blazed Cedar B.T. with the 1935 location poster still attached. He set a 3/4" aluminum rod with a 3 1/4" stamped aluminum cap and the following new B.T.s --- 14" Hemlock N.44 E. 28.00' --- 9" Cedar S.30 E. 3.54' --- "X" chiseled in a 3'X4'X5' rock S.81 W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

13.36' --- 6' Steel sign rail N.54 E. 1.6' ---

Corner recorded in Gogebic County Liber 3, Page 20 on 3/4/87.

I recovered the monument as described and the bearing trees as follows:

15"	Hemlock	N.42 E.	27.95'
9"	Downed Cedar	S.27 E.	3 1/2'
"X" chiseled	it large rock	S.80 W.	13.40'
6'	Steel sign rail	N.55 E.	1.59'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner research on file with Gogebic County records.

New bearing tree referenced:

6" Cedar S.22 E. 15.90'

Richard L. Drahn 5/11/99
GOGEBIC COUNTY SURVEYOR



Signed by Richard L. Drahn
Surveyor's Michigan License No. 21564

Date May 2, 1999