

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Received for record the
10TH day of JUNE
A. D. 1999 at 10:05 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 161;
Ramona Collins Deputy
Register of Deeds

<u>Gogebic</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T46N R.43W</u>	<u>K-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Section Corner 11, 12, 13 & 14; T.46 N., R.43 W.
I, Richard L. Drahn, in a field survey on May 26, 1999 do hereby
state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in
lines 1 and 2 above were in conformance with regulations and rules therefore as required in
the current manual of survey instructions of the United States Department of the Interior,
Bureau of Land Management or by a decree of a Court of Law and /or that the corner
points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the
Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original corner established by Austin Burt on 9/3/1851. Original bearing trees:
Cedar 10" S.35° W. 9 links (5.94')
Cedar 12" N.18° E. 18 links (11.88')

Corner restored by Richard L. Drahn, RLS 21564 on 6/4/86 from the remains of the two original B.T.s (the NE bearing tree was still
scribed. He set a 3/4" X 7' aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new bearing objects:
Steel sign rail 6' N.04° W. 9.99'
Steel sign rail 6' N.89° E. 10.17'
Steel sign rail 6' S.06° W. 10.07'
Steel sign rail 6' S.89° W. 9.67'

Corner recorded in Gogebic County Liber 4, Page 21 on 3/4/87.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I recovered the monument as described and the bearing objects as follows:
Steel sign rail 6' N.05° W. 9.91'
Steel sign rail 6' N.89° E. 10.13'
Steel sign rail 6' S.04° W. 10.11'
Steel sign rail 6' N.89° W. 9.70'

Both of the original B.T.s are now down and under water.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:
Steel sign rail 6' S.30° E. 1.77'

DEED GROUP APPROVED
Richard L. Drahn 6/9/99
COUNTY REGISTER



Signed by Richard L. Drahn Date June 5, 1999

Surveyor's Michigan License No. 21564
USFS J-21

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1985