

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Received for record the
12TH day of MAY
A. D. 1999 at 10:45 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 127
Rosanne Collins Deputy
Register of Deeds

Gogebic Located In: Corner Code #
(County)
1. Public Land Survey T46NR 43W K-8
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 23 & 24; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on May, 10 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/4/1851. Original Corner tree: Fir 6" Original B.T. --- Y. Birch 22" S.72 E. 7 links (4.62')

Corner restored by Richard L. Drahn, RLS 21564 on 7/23/75 in the stump hole of the original corner tree and at record bearing and distance from the windthrown stump hole, with Y. Birch bark of the original B.T. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s --- 8" Cedar N.24 W. 11.0' --- 9" Cedar N.54 E. 21.2' --- 9" Cedar S.17 E. 24.6' --- 7' Metal sign post N.82 E. 1.9' ---

Corner recorded in Gogebic County Liber 1, Page 148 on 1/27/76.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

10"	Cedar	N.25 W.	10.98'	(new nail)
12"	Cedar	N.56 E.	21.34'	(new nail)
13"	Cedar	S.16 E.	24.61'	(new nail)
7'	Steel sign rail	N.83 E.	1.82'	

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

12" Cedar S.85 W. 7.68'

PEER GROUP APPROVED

Richard L. Drahn 5/11/99
COUNTY REGISTERED SURVEYOR



Signed by Richard L. Drahn
Surveyor's Michigan License No. 21564

Date May 11, 1999

USFS P-21