

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County }

Received for record the
21st day of JULY
A. D. 1999 at 1:15 o'clock
8 m., and recorded in
Liber 7 of CORNERS
on page 188
Ramona Collins Deputy
Register of Deeds

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T46N R43W</u>	<u>K-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner 23, 24, 25 & 26; T.46 N., R.43 W.

I, Richard L. Drahn, in a field survey on April 23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/4/1851. Original bearing trees:

- Y. Birch 10" S.81 W. 6 links (3.96')
- Y. Birch 10" N.81 E. 16 links (10.56')

Corner restored by Richard L. Drahn, RLS 21564 on 7/14/75 from the stump remains of the two original bearing trees and from record natural feature and line tree calls. He set a 2" X 5' iron pipe with a 3" diameter stamped brass cap and the following new B.T.s:

- Sugar Maple 6" S.62 E. 25.8'
- Sugar Maple 7" S.14 E. 24.2'
- Sugar Maple 10" S.07 W. 25.8'
- Steel sign rail 7' South 1.9'

Corner recorded in Gogebic County Liber 1, Page 150 on 1/27/76.

The first original B.T. is now a very badly decayed Yellow Birch stump. The second one is now a series of root holes with Yellow Birch bark.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the monument as described and the bearing trees as follows:

- Sugar Maple 7" S.62 E. 25.63' (new nail)
- Sugar Maple 10" S.16 E. 23.96' (new nail)
- Sugar Maple 11" S.05 W. 25.38' (new nail)
- Steel sign rail 7' South 1.89'

Corner research on file with Gogebic County records.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:

- Sugar Maple 9" N.88 W. 20.98'

Richard L. Drahn 7/20/99
COUNTY REGISTRAR

Signed by Richard L. Drahn Date June 20, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, REVISED MAY 14, 1975