

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the

12 day of MAY

A. D. 1999 at 10:30 o'clock

A m., and recorded in

Liber 7 of CORNERS

on page 128

Ramona Collins, Clerk
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 46N R 43W K-10
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Quarter Corner 25 & 26; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on April 23, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/4/1851. Original B.T.s --- Hemlock 12" S.75 E. 25 links (16.5') --- Hemlock 10" N.58 W. 11 links (7.26') ---
Corner position restored by Richard L. Drahn, RLS 21564 on 7/15/75 from the remains of the two original B.T.s. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s --- 9" Sugar Maple N.64 W. 18.1' --- 6" Sugar Maple N.42 E. 31.3' --- 12" Yellow Birch S.01 W. 33.8' --- 7" Metal sign post East 1.6' ---

Corner recorded in Gogebic County Liber 1, Page 151 on 1/27/76.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:
12" Sugar Maple N.63 W. 18.03' (new nail)
10" Sugar Maple N.40 E. 31.26' (new nail)
17" Yellow Birch South 33.76' (new nail)
7' Steel sign rail N.79 E 1.56'

Corner research on file with Gogebic County records.

Both original B.T.s are present and identifiable as Hemlock stumps.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

21" Hemlock S.54 E. 28.13'

Richard P. Drahn 5/11/99
Surveyor



Signed by Richard L. Drahn

Date April 29, 1999

Surveyor's Michigan License No. 21564

USFS T-21