

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>43W</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's office }
Gogebic County } ss.

Received for record the
12 day of MAY
A. D. 1999 at 10:30 o'clock
A m., and recorded in
Liber 7 of CORNER
page 130
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 35 & 36; T.46 N., R.43 W.

Richard L. Drahn in a field survey on April 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/4/1851. Original B.T.s --- Cedar 10" S.30 W. 23 links (15.18') --- Hemlock 12" N.33 E. 19 links (12.54') ---
Corner position restored by Richard L. Drahn, RLS 21564 on 7/16/75 from the remains of the two original B.T.s and natural feature ties. He set a 2" X 5" iron pipe with a 3" stamped brass cap and the following new B.T.s --- 7" Sugar Maple N.55 E. 14.7. --- 7" Sugar Maple S.08 E. 9.5' --- 9" Sugar Maple S.52 W. 20.0' --- 7' Metal sign rail N.43 W. 2.4'

Corner recorded in Gogebic County Liber 1, Page 153 on 1/27/76.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

8"	Sugar Maple	N.54 E.	14.74 (new nail)
9"	Sugar Maple	S.11 E.	9.41' (new nail)
10"	Sugar Maple	S.50 W.	19.89' (new nail)
7'	Steel sign rail	N.41 W.	2.46'

Portions of a downed Cedar and a deep depression still remain from the original bearing trees.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

11"	Sugar Maple	N.32 W.	19.52'
-----	-------------	---------	--------

Richard L. Drahn 5/11/99
LICENSED LAND SURVEYOR



Signed by Richard L. Drahn Date April 29, 1999

Surveyor's Michigan License No. 21564

USFS X-21