

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

Received for record the
12 day of MAY
A. D. 1999 at 10:30 o'clock
A. M., and recorded in
Liber 7 of CORNERS
on page 132
Ramona Collins Depu
Register of Deeds

SECTION
For corners in

Table with columns: Gogebic (County), Located In, Corner Code. Includes entries for Public Land Survey, Property Controlling, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Quarter Corner 1 & 12; T.46 N., R.43 W.

Richard L. Drahn, in a field survey on April 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/3/1851. Original B.T.s --- Sugar 12" S.03 E. 46 links (30.36') --- Y. Birch 12" N.02 E. 39 links (25.74') ---

Corner restored by Richard L. Drahn, RLS 21564 on 5/28/86 from the remains of the two original B,T,s. He set a 2" X 36" iron pipe with a 3" stamped brass cap and the following new bearing trees:

- 12" Cedar N.11 E. 30.52'
9" Sugar Maple S.55 E. 19.20'
16" Yellow Birch S.43 W. 30.71'
6' Steel sign rail N.30 E. 1.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County Liber 3, Page 23 on 3/4/87.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows;

- 13" Cedar N.11 E. 30.50'
10" Sugar Maple S.56 E. 19.21'
17" Yellow Birch S.41 W. 30.72'
6' Steel sign rail N.30 E. 1.86'

No evidence remains of the original corner or bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- 5" Sugar Maple N.45 W. 32.39'

Richard L. Drahn 5/11/99
COUNTY REGISTER



Signed by Richard L. Drahn Date April 11, 1999

Surveyor's Michigan License No. 21564