

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Gogebic }  
County } ss.

Received for record the

12 day of MAY

A. D. 1999 at 10:30 o'clock

A m., and recorded in  
Liber 7 of CORNERS

on page 133

*Ramona Collins Deput*  
Register of Deeds

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey

T46NR43W L-7

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Quarter Corner 13 & 24; T.46 N., R.43 W.

I, Richard L. Drahn in a field survey on May 5, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 7/17/1851. Original B.T.s --- Cedar 7" S.54 W. 33 links (21.78') --- Y. Birch 12" N.40 E. 21 links (13.86') ---

Corner restored by Richard L. Drahn, RLS 21564 on 8/13/75 from the remains of the two original B.T.s. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 7" Cedar N.23 E. 15.4' --- 9" Yellow Birch N.35 E. 33.5' --- 7" Cedar N.73 W. 45.0' --- 7' Metal sign post N.13 E. 3.1' ---

Corner recorded in Gogebic County Liber 1, Page 147 on 1/27/76.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as follows:

10"	Cedar	N.21 E.	15.21'	(new nail)
10"	Yellow Birch	N.34 W.	33.69'	(new nail)
10"	Cedar	N.72 W.	44.98'	(new nail)
7'	Steel sign rail	N.11 E.	3.04'	

Portions of the original Cedar B.T. are still present. A depression is all that remains of the original Yellow Birch B.T.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

12" Red Maple S.37 E. 9.87'

DEED GROUP APPROVED  
*Richard L. Drahn* 5/11/99  
COUNTY REGISTER



Signed by Richard L. Drahn  
Surveyor's Michigan License No. 21564

Date May 6, 1999

USFS N-23