

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
10<sup>th</sup> day of JUNE  
A. D. 1999 at 10:10 o'clock  
A m., and recorded in  
Liber 7 of CORNERS  
on page 165  
Ramona Collins, Deputy  
Register of Deeds

For corners in

|                                       |                    |               |
|---------------------------------------|--------------------|---------------|
| <u>Gogebic</u><br>(County)            | Located In:        | Corner Code # |
| 1. Public Land Survey                 | <u>T 46N R 43W</u> | <u>M-2</u>    |
|                                       | <u>T R</u>         |               |
|                                       | <u>T R</u>         |               |
|                                       | <u>T 46N R 42w</u> | <u>A-2</u>    |
| 2. Property Controlling<br>in Section | S T R              |               |
|                                       | S T R              |               |
| 3. Miscellaneous<br>Property in Sec.  | S T R              |               |
|                                       | S T R              |               |

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_  
Quarter Corner 1 & 6; T.46 N., R.42-43 W.

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 10 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Richard L. Drahn, in a field survey on May 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 8/6/1847. Original bearing trees;  
Y. Birch 14" S.39° E. 12 links (7.92')  
Lynn 14" S.88° W. 15 links (9.90')

Corner restored by Richard L. Drahn, RLS 21564 on 7/20/78 from the remains of the two original B.T.s, natural feature ties and line trees north and south. He set a 2" X 4' iron pipe monument \* with a 3" stamped brass cap and the following new B.T.s:

Red Maple 5" N.40° W. 15.7'  
Yellow Birch 8" N.16° E. 30.2'  
Red Maple 13" S.52° E. 23.1'  
Steel sign rail 6' S.11° E. 2.2'

Corner recorded in Gogebic County Liber 1, Page 434 on 1/17/79.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the monument as described and the bearing trees as follows:  
Red Maple 5" N.40° W. 15.62' (new nail)  
Yellow Birch 11" N.15° E. 30.10' (new nail)  
Red Maple 13" S.53° E. 22.83' (new nail)  
Steel sign rail 6' S.13° E. 2.24'

Only a large stump hole and a shallow depression remain from the original bearing trees.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:

Hemlock 18" N.73° E. 5.78'

PEER GROUP APPROVED  
Richard L. Drahn 6/9/99  
COURT REGISTERED



Signed by Richard L. Drahn Date May 21, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975