

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

Received for record the
12 day of MAY
A. D. 1999 at 10:30 o'clock
A. M., and recorded in
Liber 7 of CORNERS
on page 135
Ramona Collins, Deputy
Register of Deeds

SECTION
For corners in

Gogebic (County)		Located In:	Corner Code #
1. Public Land Survey		T 46N R 43W	M-3
		T _____ R _____	
		T _____ R _____	
		T 46N R 42W	A-3
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

Section Corner 6, 7, 1 & 12; T.46 N., R.42-43 W.

I, Richard L. Drahn in a field survey on April 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on August 6, 1847. Original B.T.s --- 16" Y. Birch N.78 W. 25 links (16.50') --- 10" Y. Birch N.38 E. 30 links (19.80') --- 10" Y. Birch S.60 E. 73 links (48.18') ---

Corner restored by Richard L. Drahn, RLS 21564 on 7/20/78 from the remains of the three original B.T.s He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new bearing trees:

8"	Red Maple	N.10 W.	30.8'
6"	Red Maple	N.85 E.	12.5'
15"	Hemlock	S.30 W.	35.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6' Steel sign rail South 3.2'

Corner recorded in Gogebic County Liber 1, Page 436 on 1/17/79.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

11"	Red Maple	N.13 W.	30.76'
8"	Red Maple	N.83 E.	12.47'
19"	Hemlock	S.30 W.	35.37' (new nail)
6'	Steel sign rail	South	3.23'

Depressions are still evident from the first two original B.T.s and a decayed Yellow Birch stump remains from the third.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

8" Red Maple S.43 E. 38.38'

Richard L. Drahn 5/11/99
REGISTERED LAND SURVEYOR



Signed by Richard L. Drahn

Date April 11, 1999

Surveyor's Michigan License No. 21564